

Fermilab Run II Performance

RHIC Retreat, June 15-17 2005


Jim Morgan
Fermilab Accelerator Division

Some similarities and differences between RHIC and the Tevatron

- Both are Colliders with multiple experiments, halo removal, beam-beam etc.
 - Ions vs. proton-pbar
 - Fermilab has longer stores, but similar percentage of up-time and physics hours
 - Duration of runs (Typically 40 weeks for the Tevatron)
 - Fermilab shutdowns have extreme time pressure and are driven by upgrades
 - Run II is expected to end when the LHC begins taking physics data
- The Tevatron runs very close to its quench limit
- Demands on accelerators in addition to collider operations
 - FNAL injection chain required to run continually
- Roll of Run Coordinator
 - Fermilab Run Coordinator similar to RHIC's, but also
 - Handles scheduling duties including accelerator and experimental accesses (including filtering)
 - Schedules store parameters and duration as well as study periods
 - Needs to communicate plan to all interested parties
- Need to increase luminosity without too much disruption
- We have one experiment (CDF) more sensitive to backgrounds than the other (D0)
 - Our goal is to maximize integrated luminosity to tape for both experiments
- Beam position control and correction crucial
 - It was beneficial for us to instrument our low beta quadrupoles
- We worry about our budget, manpower and future too


Fermilab Complex

- The Fermilab Collider is a Antiproton-Proton Collider operating at 980 GeV




Proton Acceleration

- H⁻ ions are accelerated to 750 keV in the Crockoft-Walton
- H⁻ ions are accelerated to 400 MeV in the Linac
- H⁻ ions are stripped and multi-turn injected onto the Booster
- Protons are accelerated from 400 MeV to 8 GeV in 33 mS in the Booster
- In the Main Injector Protons are accelerated from 8 GeV
 - to 120 GeV for NuMI operation and pbar production in 2.0 - 4.0 seconds
 - to 150 GeV for Tevatron filling in 3.0 seconds
 - to Switchyard, resonantly extracted for two fixed target users
- Protons are accelerated from 150 GeV to 980 GeV in the Tevatron




Pbar production


- 1×10^8 8 GeV pbars are made every 2-4 seconds by delivering 7×10^{12} 120 GeV protons onto an Inconel target
- 8 GeV Pbars are focused with a lithium lens operating at a gradient of 760 Tesla/meter
- 30,000 pulses of 8 GeV Pbars are collected, stored and stochastically cooled in the Debuncher and Accumulator and Recycler Rings
 - The stochastic stacking and cooling increases the 6-D phase space density by a factor of 600×10^6
- 8 GeV Pbars are accelerated to 150 GeV in the Main Injector and to 980 GeV in the Tevatron (36p x 36pbar)




NuMI/MINOS



Tevatron tunnel



Collider stores over a week



Collider History

- 1986-1987 Engineering Run
 - .05 pb⁻¹
- 1988-1989
 - 9.2 pb⁻¹
- Run Ia (1992-1993)
 - 32.2 pb⁻¹
- Run Ib (1994-1996)
 - 154.7 pb⁻¹ (196 pb⁻¹ cumulative)
- Run II (2002-2009)
 - 4,000 – 8,000 pb⁻¹ planned

Changes for FY04

- **Run had been in a “commissioning” mode in FY02 and FY03**
 - Emphasis was on providing study time to meet goals
 - Progress had been well below expectations (and the run was 25% over)
 - **Philosophy shift to considering the Collider commissioned**
 - Focus changed to operating the Collider
 - Study time was primarily devoted to improving machine performance (present and future)
 - Studies required a plan and purpose
 - Study time was scheduled to minimize the impact on operations
 - Shutdowns and accesses were kept as short as possible
 - Emphasis on improving performance and reliability
 - Most aspects of operating the accelerators had become routine
 - **The competition for beam, study time, and resources between the Collider and external beam lines increased significantly in FY04**
 - Recycler was being commissioned
 - MiniBoone was operational
 - SY120 became operational
 - NuMI was gearing up to start commissioning in early FY05
 - **Provide long-term continuity for operational goals, strategy and monitoring.**
 - **Improve/clarify assignments of responsibility for**
 - study strategy and coordination
 - machine parameter targets
 - shot strategy
 - **Involve experiments directly in the decision-making process**
-

Changes for FY04 and the future

- The task for coordinating the operations of the accelerators in FY04 became the permanent responsibility of the new Integration Department.
 - The leader of the Integration Department is the Associate Division Head for Systems, Operations, and Integration.
 - This Integrations Department is divided into four wings
 - Operations Coordination
 - Shot Analysis and Strategy
 - Accelerator Physics and Accelerator Studies
 - Rapid Response Team
 - The Operations Department will assume more responsibility for operating the accelerators
 - Larger reliance on Crew Chief decision making (as in the latter part of Run I)
 - Run Coordinator provides guidelines for Crew Chief
 - Improved communication between the Run Coordinator and Experiments
 - Experiments participate in daily Integration Meeting
 - Run Coordinator elog used to disseminate information
 - Future changes
 - Run Coordinator becomes three-person team
 - A second deputy RunCo has been recently added
 - In FY06, the deputies will take on the day to day responsibilities
 - I'll be the team leader, concentrating on shot analysis, operational and studies priorities
 - Associate Division Head becomes more involved in problem areas
 - Will lead Rapid Response Teams when appropriate
 - Has been involved with planning what happens after Run II
 - Rapid Response team may merge with Accelerator Physics
-


Run Coordinator's Responsibilities

- **Create and coordinate the operational planning for the accelerator complex**
 - Run daily Integration Meeting to discuss and formulate the operational plan
 - Schedule Recycler and Collider transfers
 - Coordinates studies and commissioning activities
 - Tevatron and accelerators, SY120, Recycler, Ecool and NuMI
 - Also NTF, MTA and MuCool
 - Schedule accelerator studies
 - Schedules shutdowns and maintenance
 - Evaluates and oversees operational policies of Systems Departments
 - Monitors peak operating performance of the accelerators
 - Receives and coordinates requests from the experiments
- **Operational planning and coordination now the primary focus**
 - Long range planning and presentations are handled by Associate Division Head
 - Creation of integration team reduces the burden on the Run Coordinator
- **Uses input from other groups within the Integration Department in decision making**
 - Shot analysis, evaluating studies requests etc. is now a group effort
- **Run Coordinator is no longer a 4-month term**
 - Provide long-term continuity for operational goals, strategy and monitoring
 - Part of the work load is shifted to other members of the Integration and Operations Departments

Communications

- **The primary tool for communications is the DAILY Operations Meeting**
 - This meeting
 - Is short (20-30min) and focused
 - Has a well defined agenda and goals
 - To keep communication open and direct, attendance to this meeting is limited
 - At most 2 representatives from each system in which one is the machine coordinator
 - At most 2 representatives from each support department
 - At most 2 representatives from each experiment
 - The Friday meeting is open to anyone and also has weekly reports from the various machines
 - At the end of the meeting the systems, support departments, and the experiments know exactly when the plan for the day is
 - This plan is summarized as an entry in the Run coordinator elog for the rest of the lab to read
 - Changes in the plan are communicated via the MCR Operators and Run Coordinator elog
 - **An important basis for communications is Shot Data Analysis (SDA)**
 - SDA
 - Rapidly identifies under (or over) performing systems
 - Is used for judging performance of systems at the daily operations meeting.
 - Is used for predicting future performance
 - Eliminates many conversations that begin with “I remember when we had a store that...”
 - A large number of standardized plots are produced daily and posted on the web
 - Important analysis
 - Single store snapshot
 - Parameters as a function of store number
 - SDA consists of
 - A dedicated database
 - Tools for setting up automated acquisition of data into the data base
 - Tools for retrieving data from the database
-

Luminosity projection for FY04



Major Accomplishments in FY04

- **Proton Source**
 - Operational Improvements
 - Booster Aperture
 - Alignment of Booster cavities and Magnets
 - Long 3 septum
 - New dogleg magnets at Long 3
 - Removal of beta wave
 - Less tune shift
 - Damper mode number and Power increase
 - Matching of the 400 MeV Line
 - Harmonic Correction
 - Two stage collimation system
 - Records
 - Record intensities- 6.0×10^{12} protons/pulse
 - Record Efficiencies $> 85\%$
 - Record Throughput
 - $> 6.8 \times 10^{18}$ protons/week
 - $> 6.0 \times 10^{16}$ protons/hour
 - $> 4.5 \times 10^{17}$ protons/shift
 - **Antiproton Source**
 - Stacking rate 13.65×10^{10} pbars/hour
 - Largest stack 246×10^{10}
 - Longest sustained stack > 2 months
 - Debuncher Aperture Increase
 - Main Injector – Debuncher Phase alignment system
 - Aperture Increase
 - 8 GeV alignment across the injector complex now possible
-

Major Accomplishments in FY04 (cont.)

- **Recycler**
 - Recycler bake-out was extremely successful
 - Transverse emittance growth reduced by a factor of 4-5
 - Recycler shots to the Tevatron
 - Initial Luminosity $> 17 \times 10^{30} \text{cm}^{-2} \text{sec}^{-1}$
 - Integrated useable luminosity
 - Stack of $> 150 \times 10^{10}$ pbars in the Recycler
 - Recycler was put into Mixed Source operations
 - Recycler was ready for Electron Cooling
- **Tevatron**
 - Lifetime at 150 GeV
 - Larger Aperture, alignment and dipole un-rolls
 - Use of Octupoles to control differential chromaticity
 - Emittance dilution reduced
 - Smart bolt retrofit -> de-coupling at TEV injection
 - Optimization of injection optics
 - CDF IP
 - Location of IP was 4-5 mm too high vertically
 - Significant impact on CDF's
 - Silicon tracking efficiency
 - SVX longevity due to radiation damage
 - Rapid response team was organized during the 1 week shutdown in early December (due to the 16 house quench) to find a solution to move the CDF IP down by 4 mm
 - New Low Beta Optics
 - 20% increase in luminosity

FY04 Machine Issues


- **Linac**
 - Availability of low energy Linac RF Power tubes
 - Klystron spare viability
- **Booster**
 - Radiation damage due to the proton demands of the neutrino program.
 - Running at record throughput
 - Commissioning cogging (needed for slip-stacking and NUMI)
 - Preliminary stages of developing a proton plan
 - Pulse component upgrade
 - Aperture upgrade (RF stations and kickers)
 - Alignment upgrade (TEV style alignment network)
 - Closed orbit control (ramped magnets and power supplies)
- **Pbar Production**
 - Increase transverse aperture of AP-2 and the Debuncher
 - Greatly improve D/A transfer at fast cycle times
 - Minimized the Momentum Spread in the Debuncher
 - Increase the bandwidth of the Debuncher Momentum cooling system (~20%) with equalizers
 - Optimize gain and gain ramping in the Debuncher momentum cooling
 - Investigate a static change in gamma-t in the Debuncher
 - Trade-off of bunch rotation bucket are vs good mixing for the accumulator
 - Investigate the feasibility of ramping gamma-t in the Debuncher

FY04 Machine Issues (cont.)


- **Recycler**
 - Transverse emittance growth is NO LONGER an issue
 - Recycler bake-out was extremely successful
 - Transverse emittance growth reduced by a factor of 4-5
 - Mixed Source Mode Operations
 - Injection and Extraction Transfer mechanics
 - Transverse stochastic cooling cooling rate
 - Longitudinal emittance dilution
 - During injection and extraction
 - During storing
 - Beam stability
- **Tevatron**
 - More magnet unrolls and cold lifts required during shutdown
 - Ready for additional separator to be installed during shutdown
 - Need to determine benefit of further upgrades
 - Improve protection to experiments and components from beam loss

FY04 Lessons


- **Tevatron Abort**
 - Because of the Experiments' silicon detectors, we cannot tolerate "messy" aborts
 - A single messy abort triggers a TEV study to determine cause and fix
 - A procedure to verify that the abort system is working properly.
 - Examine the possibility of a hardware system that can detect if the abort system is functioning
- **Tevatron Beam Energy**
 - 1MegaJoule in beam energy
 - Review of the policy for masking aborts
 - Reduce the time between the initiation of beam loss and abort
 - Quench protection upgrade solved the problem



Peak Luminosity



Integrated Luminosity




FY04 Summary

- **Collider performance in FY04**
 - Delivered 345 pb^{-1} in 39 weeks (8.8 pb^{-1} per week)
 - The peak luminosity and the luminosity per week has doubled from FY03
 - Most of the Tevatron parameters are close to the design values
 - The Proton Source is operating at record intensities, efficiencies, and throughput.
 - Slip Stacking has been commissioned in the Main Injector
 - The Recycler was:
 - ready for electron cooling
 - Dramatically increased peak luminosity through mixed-pbar operations
 - Pbar production is well below the design parameters but the study plan executed over the summer indicates that the source of the shortfall is the result of a small effective aperture in the D-A line
- **FY05 will be a pivotal year for the Run II Collider**
 - Pbar stacking
 - Mixed Pbar operation
 - Electron cooling installation and commissioning
 - NUMI Commissioning and Running
 - MiniBoone and SY120 continue
 - Not enough protons to go around


Plans for FY05

- Demonstrate electron cooling of antiprotons by the end of FY05
- Run Slip Stacking at 8×10^{12} protons/pulse every 2 secs
- Increase the pbar production aperture by 25%
- Stack at small stacks with a rate of $18\text{-}24 \times 10^{10}$ pbars/hr
- Run the complex in Mixed Pbar operations
 - Assume the gain from Mixed Pbar operations is at least “break-even” on integrated luminosity
- Run NUMI at a 2 sec. cycle time with 2.5×10^{13} protons/cycle by the end of the year
 - Keep activation levels in Booster at the April 29, 2004 level.
- Continue to run MiniBoone and SY120
 - Will need guidance from Program Planning on the priorities of NUMI, MiniBoone, SY120
- Integrate 470 pb^{-1} in 34 weeks (average $\sim 14 \text{ pb}^{-1}/\text{week}$)

FY05 Goals Integrated Luminosity



FY05 Goals Peak Luminosity




Combined Shots


- **Extracting antiprotons from both the Accumulator and the Recycler for the same store i.e.**
 - Twelve bunches from the Recycler
 - Twenty four bunches from the Accumulator
 - **Combined Shot Operation**
 - Proposed in February '04
 - Initial proposal presented at the April '04 Run II PMG
 - Dual energy ramps in the MI completed and tested by May '04
 - First Attempt 6/13/04
 - Record Luminosity
 - $103 \times 10^{30} \text{cm}^{-2} \text{sec}^{-1}$ recorded July 2004
 - $127 \times 10^{30} \text{cm}^{-2} \text{sec}^{-1}$ recorded May 2005
 - Routine Operations - January 2005
 - **Reasons**
 - Flexibility in the Run II Upgrade schedule
 - Natural merging of commissioning of electron cooling
 - Push Recycler commissioning progress by plunging it into operations
 - Luminosity enhancement – larger amount of antiprotons for smaller emittances
 - Accumulator stack size limited to <200 mA
 - Stacking Rate
 - Transverse emittance vs Stack Size
 - **Ratio $I_{\text{Recycler}}/I_{\text{Accumulator}}$ is governed by:**
 - Recycler phase space density (cooling)
 - Recycler transfer time (Rapid transfers)
 - **Obstacles**
 - Stacking Rate
 - Injector Complex 8 GeV energy alignment
 - Longitudinal emittance in both the Accumulator and Recycler
 - Transfer time between Accumulator to Recycler
-

Pbar stacking performance


SSR = 12.36 mA/hr Max Stack = 285.37 mA K = 97.52 % For Store 323




SSR = 12.36 mA/hr Max Stack = 285.37 mA K = 97.52 % For Store 323




Accumulator Stack Size vs. Transverse Emittance



Accumulator to Recycler Antiproton Transfers




- Transfers between the Accumulator to the Recycler take about 1 hour to accomplish
 - Presently 1 or 2 sets of transfers to support a collider store
- To realize the full potential of electron cooling, in the Recycler, this time needs to be reduced to less than 15 minutes with >90% efficiency
- Adopt a philosophy of being willing to lose a pbar transfer occasionally
 - Transfers frequency eventually faster than every 2 hours




Electron Cooling



- The maximum antiproton stack size in the Recycler is limited by
 - Stacking Rate
 - Longitudinal cooling in the Recycler
- Longitudinal stochastic cooling of 8 GeV antiprotons in the Recycler is to be replaced by Electron Cooling
 - Electron beam: 4.34 MeV – 0.5 Amps DC – 200 μ rad beam spread – 99% recirculation efficiency
- Installation of e-cool equipment in MI-31 and the Recycler tunnel complete
- Commissioning of electron cooling in progress
 - Electron beam circulated in cooling section
 - Commissioning due to be completed by September 2005







Luminosity in Run II




- **Luminosity increase is mostly due to:**
 - Decision to “run” the Collider
 - Rigorous approach to attacking operational problems
 - De-emphasis of long periods of dedicated machine studies
 - Better performance of the injector chain
 - Faster pbar stacking because of increased protons on target
 - Alignment of the Tevatron
 - Introduction of the Recycler into operations

Other Business - Fixed Target FY05 Accomplishments

- **Record throughput for MiniBoone**
 - 8.0×10^{16} protons/hour
 - Delivered a over 5×10^{20} protons in under three years of running
- **Routine running of Mixed Mode for SY120 with slip-stacking for pbar production**
 - A factor of 7 more spill seconds then originally allocated
 - And they're still unhappy
 - NUMI has taken the place of SY120 on the antiproton stacking cycles, a new long flattop ramp has kept about half of the spill-seconds intact (with a 5% hit to NuMI and pbar production).
- **NUMI commissioned**
 - First beam on Dec. 4, 2004
 - Around the clock operations on March 14, 2005
 - Target problems April 2005
 - Have resumed operations in Mixed-Mode antiproton stacking cycles

Integrated Luminosity in Run II



Summary

- **Since last year's retreat, the Tevatron has seen:**
 - 60% increase in peak luminosity
 - 40% increase in integrated luminosity per week
 - 100% increase in integrated luminosity for Run II
- **Luminosity increase is mostly due to:**
 - Better performance of the injector chain and faster stacking (up to 16E10/Hr)
 - Introduction of the Recycler into operations
 - Decision to “run” the Collider
 - Rigorous approach to attacking operational problems
 - De-emphasis of long periods of dedicated machine studies
- **The Run II Upgrades are on track to provide more than 4fb⁻¹ by 2009**
 - The Recycler is operational
 - Electron cooling is progressing well
 - Slip Stacking is operational
- **The major challenges left in Run II centers on antiprotons**
 - Commission electron cooling in the Recycler
 - Increase the antiproton production rate
 - AP2- Debuncher aperture upgrade, Lens upgrade
 - Debuncher to accumulator transfers, stacktail momentum upgrade
 - More protons on target with acceptable losses in the Main Injector
 - Rapid transfers between the Accumulator and Recycler, fast and efficient